



# INSTITUTE FOR SOCIAL AND ECONOMIC CHANGE

Nagarabhavi PO: Bengaluru - 560 072

Phone : 23215468, 23215519, 23215592 FAX: 91-080 23217008 INDIA E-mail : admn@isec.ac.in

AN ALL INDIA INSTITUTE FOR INTER-DISCIPLINARY RESEARCH & TRAINING IN THE SOCIAL SCIENCES

*Shri S Ashok Rao*  
*Registrar*

Ref: ISEC\AMC CCTV-WiFi-Audio-Visual\2022-23\609 24<sup>th</sup> November, 2022

**Sub: Quotation for AMC for CCTV Network, WiFi Network and Audi-Visual Setup**

Dear Sir/Madam,

1. Enclosed herewith is the Quotation form for AMC for CCTV Network, WiFi Network and Audio Visual Equipments
2. In case you are interested, please submit your competitive quotation as per the specification given in the enclosed form in a sealed envelope addressed to the Registrar on or before 5.00 p.m., 6<sup>th</sup> December 2022. The Envelope should be super-scribed as **QUOTATION FOR AMC OF CCTV, WiFi AND AUDI-VISUAL**
3. You may visit the Institute to view the Systems in place during office hours from 10.00 AM to 5.00 PM before AMC quote.

Thanking you,

Yours Sincerely,

  
(Registrar)

## Normal Conditions of AMC

1. The AMC will be entered into for a period of 1(one) year *(Preventive)*
2. You may kindly quote for both the Non-Comprehensive AMC and Comprehensive AMC as indicated in the attached Table
3. The comprehensive AMC should cover all the costs including any spares to be used.
4. The preventive maintenance must be done once in 3 months and should submit the report about the same.
5. Attending to the breakdown or repair calls shall be attended within 24 hours of the reporting.
6. The AMC charges, 50%, will be paid after entering into the contract after raising the invoice and the next 50% after completion of the six months period.

Date:

To

The Registrar  
 Institute for Social and Economic Change  
 Dr. V K R V Rao Road, Nagarabhavi, Bangalore - 560 072

AMC for CCTV Network, WiFi Network and Audio Visual Equipment			
Sl. No	Description	Non-Comprehensive AMC	Comprehensive AMC
<b>CCTV Network</b>			
1	<p><b>Campus wide CCTV system</b> was established during May,2017 with 1Gb fiber backbone distributed in Admin, seminar block, Ladies hostel and Main gate. Each block has wall mount rack equipped with PoE switch, Fiber LIU, UPS and UTP structured cabling to connect 19 cameras . Hikvision cameras are configured and centrally managed by NVR. 3 networked client machines with LED display are connected across the campus for viewing. List of the major components used are:</p> <p>2 MP PTZ camera = 3 nos</p> <p>2 MP fixed bullet camera = 8 nos</p> <p>2 MP varifocal bullet camera = 8 nos</p> <p>32 channel NVR with 4TB HDD= 1 no</p> <p>Gigabit PoE managed switch = 4 nos</p> <p>Desktop with 32"/22" LED display = 3 nos</p> <p>Fiber cable &amp; accessories = 650 mts</p> <p>UTP cable &amp; accessories = 4 box</p> <p>600 VA UPS = 5 nos</p>		

<b>AMC for CCTV Network, WiFi Network and Audio Visual Equipment</b>			
<b>Sl. No</b>	<b>Description</b>	<b>Non-Comprehensive AMC</b>	<b>Comprehensive AMC</b>
2	<p><b>WiFi Network</b>  Campus wide WiFi network was established during March,2016 with 1Gb fiber backbone distributed in Admin, seminar block, guest house, Men's hostel, Ladies hostel. Each block has wall mount rack equipped with PoE switch, Fiber LIU, UPS and UTP structured cabling to connect 26 Access Points. Sophos APs are configured and centrally managed by Wireless controller. List of the major components used are:</p> <p>Wireless Access Points = 32 nos  Wireless controller = 1 no  Gigabit PoE managed switch = 4 nos  Fiber cable &amp; accessories = 500 mts  UTP cable &amp; accessories = 4 box  3 KVA online UPS with 8x130AH external with battery bank 1 set  800 VA UPS = 3 nos  1 KV UPS = 2 nos</p>		
<b>Audio-Visual Equipments in Seminar Room</b>			
3	<p>Ceiling mounted LCD Projector :  Panasonic PT-VW360 : <b>2 Nos</b>  55" Full HD LED Panasonic TV : <b>4 Nos</b>  Facepalte with VGA/Audio/HDMI connectivity: <b>2 nos</b>  Cross/Up convertor - Video/PC/HD/Stero to HDMI : <b>2 Nos</b>  1x4 HDMI V1.4DA: <b>2 Nos</b>  HDMI Audio Breakoutinput : <b>2Nos</b>  Transmitter HDMI ver 1.4 and IR : <b>4 Nos</b>  Receiver HDMI ver 1.4 : <b>4 nos</b>  Equipment Rack 9U: <b>1 Nos</b>  1 KVA APC UPS: 3 Nos</p>		
<b>Total</b>			
<b>GST @</b>			
<b>Grand Total</b>			

(Authorized Signatory with Company name & seal)